

Upcoming Bid Projects

Bob Mays Park

Cedar Creek Trail Project

Plans are available from the IDOT web site: www.dot.state.il.us

Go to Letting and Bidding section

See Item #83, Contract No. 93454 Adams County District 6

Section 99-P4003-01-BT

CEDAR CREEK TRAIL Project ACHPP-HPP-1985(1)

Construct a pedestrian/bike trail including 2 prefabricated Truss bridges, 10' wide bituminous pavement, sidewalk, drainage, retaining walls and seeding along Cedar Creek linking parks and residential areas from North 12th Street to Bob Mays Park in Quincy; includes 32 trees; 1,920 sq ft pedestrian truss

Superstructure; 233 sq ft segmental concrete block wall; underwater structure excavation protection; 788 ft fence; 3.3 acre tree removal; 7,820 cu yds earth excavation; 47.7 cu yds rock excavation; 4,220 cu yds furnished excavation; 3.5 acre seeding and mulch; 936 lbs fertilizer nutrient; 3,367 ft perimeter erosion barrier; 1,818 tons stone dumped riprap; 8,905 sq yds aggregate base course; 500 tons HMA surface; 61 sq yds bridge approach pavement; 7,150 sq ft PCC sidewalk; 44 sq ft detectable warnings; 3,147 sq yds aggregate shoulders; 313.3 cu yds concrete structures; 20,610 lbs reinforcement bars; 222 ft pipe culverts; 62 ft storm sewers; 270 ft electric cable in conduit; 202 sq ft sign panels; 4,652 ft pavement marking; traffic control and protection; Federally funded. (70 Working Days) (Job No. C-96-216-08) (6-10271-0000) (10.00% DBE)